

HOUSE
CONSTRUCTION OF: WALLS, CEILINGS, ROOF
Plinth
Damp proof insulation on the perimeter of the house in the form of EPDM membrane in accordance with details
External walls $U=0.09 \text{ W}/(\text{m}^2\text{K})$
Render, colour white
Thermal insulation - polystyrene facade, $\lambda=0.031 \text{ W}/(\text{mK})$ - 200 mm
OSB sterling board/chipboard - 12 mm or gypsum fibre board 12.5 mm ¹
Timber studs (of resinous wood) - 180 mm
Thermal insulation - mineral wool, $\lambda=0.035 \text{ W}/(\text{mK})$ - 180 mm
OSB sterling board/chipboard - 12 mm or gypsum fibre board 12.5 mm ¹
Polyethylene vapour check
Plasterboard - 12.5 mm
Internal walls
Plasterboard - 12.5 mm
OSB sterling board/chipboard - 12 mm or gypsum fibre board 12.5 mm ¹
Timber studs (of resinous wood) - 180 mm/120 mm/80 mm
Insulation - mineral wool - 50 mm
OSB sterling board/chipboard - 12 mm or gypsum fibre board 12.5 mm ¹
Plasterboard - 12.5 mm
Ground floor layers ²
Flooring according to the individual room description
Screed - 65 mm
Thermal insulation - 90 mm
Damp proof membrane (if foundations are on the ground)
Floor/ceiling over the ground floor layers
Flooring according to the individual room description
Screed - 65 mm
Thermal insulation - polystyrene boards - 80 mm
OSB sterling board/chipboard - 22 mm
Timber joists (of resinous wood)/trusses - 220 mm
Insulation - mineral wool - 50 mm
Timber battens for plasterboards ³
Plasterboard - 12.5 mm
Floor/ceiling over the ground/first floor layers (between heated and unheated spaces)
Timber walk boards - 22 mm (width approx. 1 m)
Thermal insulation - mineral wool, $\lambda=0.035 \text{ W}/(\text{mK})$ - 320 mm (370 mm 1.5- storey houses) ⁴
Timber joists (of resinous wood)/trusses - 220 mm
OSB sterling board/chipboard - 22 mm
Polyethylene vapour check
Plasterboard - 12.5 mm
Gable/hip roof without insulation ⁵
Cement roof tiles according to the samples
Roof battens
Counter battens
Breathable membrane
Timber rafters (of resinous wood)/trusses
Gable roof over inhabited space ⁵
Cement roof tiles according to the samples
Roof battens
Counter battens
Breathable membrane
Timber rafters (of resinous wood)/trusses - 300 mm
Thermal insulation - mineral wool, $\lambda=0.032 \text{ W}/(\text{mK})$ - 300 mm ⁶
OSB sterling board/chipboard - 22 mm
Polyethylene vapour check
Plasterboard - 12.5 mm
Flat roof
Gravel ballast with min. thickness 50 mm
EPDM foil
Mineral wool thermal insulation thickness - 230 mm

Vapour barrier
OSB sterling board/chipboard - 22 mm
Timber joist - 220 mm
Timber battens for plasterboard
Plasterboard - 12.5 mm
HOUSE EXTERNAL
ROOF COVERING
Concrete roof tiles, type and colour according to the samples
GUTTERING
Half-round PVC guttering, with matching down pipes taken to 15 cm below DPC level. Colour according to the samples
ROOF WINDOWS
PVC, double glazing, $U_g=1.0 \text{ W}/(\text{m}^2\text{K})$; $U_w=1.1 \text{ W}/(\text{m}^2\text{K})$ for glass, all windows with clear glazing, if applicable
EAVES, FASCIAS & SOFFITS CLADDING
Fibre cement boards fixed to battens with system screws or render, according to the architecture, painted white
BALCONY / FRENCH BALCONY / ROOF TERRACES
Steel balustrade with glass filling according to samples
Balcony decking made of pressure-impregnated larch timber boards. Colour according to the samples
WINDOWS AND BALCONY DOORS
PVC (6 chambers), colour white, inward opening, tilt and turn, triple glazing, $U_g=0.5 \text{ W}/(\text{m}^2\text{K})$ for normal glass, $U_w=ca. 0.75 \text{ W}/(\text{m}^2\text{K})$ (for the reference window 1.23 m x 1.48 m), all windows with clear glazing ⁷ . Safety glazing where required. Lockable handles
Inside the strained window there is a steel column. Colour according to the samples
Windows opening according to the project
EXTERNAL WINDOW SILLS
External aluminium window sills. Exit step in area of ground floor terrace window and first floor balcony exit (if exists). Colour according to current offer/samples.
EXTERNAL DOORS
White PVC, thermally efficient with high security multi-point locking and ironmongery according to samples. Clear glazing (safety glazing available), $U_D = 1.1 \text{ W}/(\text{m}^2\text{K})$
HOUSE INTERNAL
INTERNAL DOORS
Internal doors smooth, laminated, colour according to the samples
Handles according to the samples
INTERNAL WINDOW BOARDS
For the windows with toilet frame under the window - tiled sills. For all other windows - marble window boards, colour according to the samples.
INTERNAL STAIRCASES
Stringer stairs of glued beech wood, open, transparent varnished with balustrades, according to actual offer
Folding loft ladder to attic area with a white hatch
INTERNAL WALLS
WC/Bath/En-Suite
Wall tiles, height about 1.2 m from floor level (up to ceiling around showers - max 2.52), arrangement according to the samples, remaining area filling and painting colour white
Joint grout, colour according to the samples
Tiled external wall corners finished with strips according to the samples. All horizontal transitions from tiles to paint surface finished without strips.
Other rooms
Filling and painting colour white or Raufaser wallpaper painted white
Technical room walls painted white with dispersion paint
FLOORS ⁸
Kitchen/Technical room
Floor tiles, size and arrangement of tiles according to the samples
Joint grout, colour according to the samples
Terracotta skirting board, colour according to the samples
Entrance
Floor tiles, size and arrangement of tiles according to the samples
Joint grout, colour according to the samples
MDF skirting for laminate, colour according to the samples

WC/Bath/En-Suite	Other
Floor tiles, size and arrangement of tiles according to the samples	Distribution board with its content and connection of meter box located in technical room - Danwood supply and install
Joint grout, colour according to the samples	Antenna (TV): 2 connection points with cable brought to attic space
Other rooms	Telephone installation: 1 telephone socket
Laminate, according to the samples	Data: 1 connection point with cable CAT6 brought to technical room
MDF skirting for laminate, colour according to the samples	Detectors: type and quantity according to local regulations
Finishing	Bell installation in the hall
Floor connections (depending on combined areas), anodised aluminium, according to the samples	1 attic double socket
Floor ventilation grills, white steel	Lighting, switches & sockets inside the house
CEILING	Living, Living/Dining: 4 double electric sockets, 2 ceiling cable outlets with 1 one-way switch
Filling and painting colour white	Bedroom, Dining, Study-Office, Family room: 2 double electric sockets, 2 single electric sockets, 1 ceiling cable outlet with 1 one-way switch
WC/BATH/EN-SUITE FITTINGS	Kitchen: 3 double electric sockets, sockets for oven and hob with switches, sockets for fridge and dishwasher with switches, single extractor hood socket, ceiling cable outlet with one-way switch
Fittings: Single lever mixer taps, according to the samples	Hall: 2 single electric sockets, 1 ceiling cable outlet with 2 two-way switches
Branded sanitary ware in white is installed as standard in the bathroom and toilet.	Landing: 2 single electric sockets, 1 ceiling cable outlet with 2 two-way switches and 1 auxiliary switch
Quantity of units and their layout according to the architectural drawings	Wardrobe, Entrance, Storage, Pantry: 1 single electric socket, 1 ceiling cable outlet with 1 one-way switch
HOUSE SERVICES ⁹	Cupboard: no electrical equipment
HEATING	Bath, WC, En-Suite: 1 shaver socket, 1 ceiling cable outlet with 1 one-way switch, 1 wall cable outlet
Heating package (options)	Technical room: 1 double electric socket, 2 single electric sockets, 1 ceiling cable outlet with 1 one-way switch
Heating package Air Source Heat Pump with hot water cylinder ⁹	Lighting, switches & sockets outside the house
Heating distribution & pipework	Outer wiring system: 1 wall cable outlet for outer lighting close to main entrance with switch inside the house, 1 external socket, 1 wall cable outlet for outer lighting on balcony and terrace with switches inside the house and 1 output socket for car charger.
Heat distribution by water underfloor heating. One electrical towel radiators in bathrooms and en-suites.	Garages integrated into the house (if applicable)
Insulated PVC pipes in accordance with applicable regulations	All integrated garages have a wall and roof structure the same as the house. The internal wall between the house and the garage is made of 180 mm timber studs with a mineral wool filling. The ceiling sheathing is made of 12.5 mm gypsum plasterboard. If increased fire safety protection is required, this will be considered for an additional fee, as far as technically possible. The vapour barrier from the outer wall is glued from the inside to the base of the foundation. Windows and side entrance doors are in white (if any). The garage is equipped with a white sectional door without an electric drive. If the door is over 5 m wide, an electric drive, socket and switch is included, as well as an electrical installation with three sockets, two ceiling lighting points and a double switch. Fuses for the electrical installation of the garage are located in the distribution board of the house. The walls and ceilings of the garage are filled and painted with white dispersion paint. The garage is layered with cement screed with a slope of 0.75% towards the garage door and a minimum thickness of 40 mm. Construction of the garage does not include finishin
MECHANICAL VENTILATION WITH HEAT RECOVERY SYSTEM	
Ventilation device installed in technical room	
Ducting: Flat ducts installed under the screed; manifold inspection box; ceiling, floor or wall inlets and outlets	
Pipework: Air intake and exhaust outlets in external walls (if applicable)	
PLUMBING INSTALLATION ¹⁰	
Hardware & pipework	
All taps are of one-lever type according to the samples	
Cold water, hot water and sewer pipes of PVC. All pipeworks included up to the boiler	
Washing machine connection	
1 washing machine surface mounted connection in technical room, 1 surface mounted sink connection with double valve for dishwasher	
Water connection outside the building	
1 external antifreeze water connection on elevation wall, in the zone of technical room or kitchen	
ELECTRICAL INSTALLATION	
Electrical fittings	
Switches and sockets: colour white	
Exemplary combinations of switches and sockets - colour white, combination according to the samples	
Doorbell: colour according to the samples	

Key:

- 1 According to the Danwood production standard in force at the time of manufacture. The U-value only applies to standard components with wood-based panels. This can individually depending on the required construction (wood content and special solutions).
- 2 The foundation slab must be insulated with at least 120 mm of insulation with a thermal conductivity of 0.041 W/(mK).
- 3 Additional substructure in bathrooms, WCs and technical rooms can lower the level of the ceiling.
- 4 Some houses may require 470 mm of insulation to meet thermal requirements.
- 5 The roof cross section may change due to construction standard requirements and type of covering.
- 6 For 1.5-storey houses with an opening to the ridge, the structure is can be (when necessary) extended with additional 60 mm battens and 60 mm mineral wool $\lambda=0.030$ [W/(mK)].
- 7 If it is a special glass construction, windows may have parameters other than the standard window.
- 8 After installation of the floor covering there may be a difference in level caused by the thickness of materials used in the flooring. Any unevenness can be leveled using treshold strips.
- 9 The installations in the technical room are surface mounted. Capacity of hot water cylinder, depends on the size of the house. In consideration of Building Regulations Part O (Overheating), there is sometimes a necessity to shade the house by installing blinds or other coverings. Their cost is not included in the price of the house.
- 10 Plumbing installation does not include automatic fire suppression systems. Should any work on the building be necessary, Danwood will offer and carry out these measures – as far as technically feasible – for an additional charge.

General: The price includes two versions of architectural drawings. If there are differences between design documentation/architectural drawings and the construction's description/specification then the latter prevails.

Note: Installation of foundation slab, services incoming to the slab, plinth finish, kitchen units, pipework from the incoming fuel source to heating appliances, and internal gas installations are supplied by the customer.